Am An GEO CONSULTANT

NAGARAJ MOKASHI, MSc.,
GEOLOGIST

Mobile : 94483 13401
e-mail : ngmokashi@rediffmail.com
am.an4geoconsultant@gmailcom

Ramjyothi Nagar, R.V.College Post, Bangalore - 560 059.

To,
AEE, BBMP
Yelahanka Sub Division.

AE: 2
Ge

Executive Engineer
Asst. Exe. Engr.
Yelahanka Sub. Divison
(Hosur Ynk. Zn)
Yelahanka, Bangalore

Date : 25/09/17

GEO-TECHNICAL SURVEY REPORT
(Ground Water Exploration)

Sir / Madam,

As per your work order/request Geo-Hydrological / Geo-physical Survey carried out in your land / site belonging Arvalli Govt. Schl (W.No.2) city/village Bangalore Dated on 25-09-17 in order to assess the ground water potential of the area for drinking / irrigation / industrial purposes.

The area inspected has a slope towards ..... marked by ..... Soil, uneven topography hydrogeological features are found to be favourable / not favourable for ground water extraction. Geology of the area is marked by Soft rock.

SOURCES EXTRACTED :

(I) Betwen 280 mtr ft/mtrs. (II) 300 mtrs ft/mtrs.

(III) ..... ft/mtrs.

From the study of the above field observation, Investigation results, a borewell VES drilling 270 to app depth of 290 ft/mtrs. Below the ground level, casing pipe required be to app depth of 200 - 280 ft/mtrs.
Approx, yield expected may be around 2 1/2 Inch GPH.

Suggested to drill 4 1/2" / 6 1/2" dia Borewell.

****

NOTE : Although the best site for drilling has been suggested, no guarantee of success can be given and we will not be liable in any way for any loss to the party in respect of the well drilled at the site recommended being a failure in any form.

Save Water

(NAGARAJ MOKASHI)

SAVE ENVIRONMENT **ADOPT RAINWATER HARVESTING**

Services : Ground Water location by geo-hydrological, geophysical and divining methods, Driling advisors and supervision. Rain Water harvesting, water shed management, Quarry operations, Planning, Water testing, Soil Testing & Surveying.

Am An GEO CONSULTANT

NAGARAJ MOKASHI, MSc.,
GEOLOGIST

Mobile : 94483 13401
e-mail : ngmokashi@rediffmail.com
am.an4geoconsultant@gmailcom

Ramjyothi Nagar, R.V.College Post, Bangalore - 560 059.

To,

AEE. BBMP
Yelahanka Sub Division.

AE.2

Date : 26/09/17

Asst. Executive Enginee
Yelahanka Sub. Divison
(RR-IV Ynk Zn)
Yelahanka, Bangalor

GEO-TECHNICAL SURVEY REPORT
(Ground Water Exploration)

Sir / Madam,

As per your work order/request Geo-Hydrological / Geo-physical Survey carried out in your land / site belonging Agrahara Bangalore city/village Agrahara KEB Layout (WARD) Dated on 26.09.17 in order to assess the ground water potential of the area for drinking / irrigation / industrial purposes.

The area inspected has a slope towards ..... marked by ..... Soil, uneven topography hydrogeological features are found to be favourable / not favourable for ground water extraction. Geology of the area is marked by ..... rock.

SOURCES EXTRACTED :

(I) Betwen 240.0 ft/mtrs. (II) 260.0 ft/mtrs.

(III) 310.0 ft/mtrs.

From the study of the above field observation, Investigation results, a borewell VES drilling .....to app depth of ..... ft/mtrs. Below the ground level, casing pipe required be to app depth of 150-180 ft/mtrs.

Approx, yield expected may be around 2½ Inch GPH.

Suggested to drill 4 ½" / 6 ½" dia Borewell.

****

NOTE : Although the best site for drilling has been suggested, no guarantee of success can be given and we will not be liable in any way for any loss to the party in respect of the well drilled at the site recommended being a failure in any form.

Save Water

(NAGARAJ MOKASHI)

SAVE ENVIRONMENT **ADOPT RAINWATER HARVESTING**

Services : Ground Water location by geo-hydrological, geophysical and divining methods, Drilling advisors and supervision. Rain Water harvesting, water shed management, Quarry operations, Planning, Water testing, Soil Testing & Surveying.

Am An GEO CONSULTANT

NAGARAJ MOKASHI, MSc.,
GEOLOGIST

Mobile : 94483 13401
e-mail : ngmokashi@rediffmail.com
am.an4geoconsultant@gmailcom

Ramjyothi Nagar, R.V.College Post, Bangalore - 560 059.

To,
AEE, BBMP
Yelahanka Sub Division

Executive Engineer
Yelahanka Sub Division
(BBMP Ynk. Zn)
Yelahanka, Bangalore

Date : 24/09/17

GEO-TECHNICAL SURVEY REPORT
(Ground Water Exploration)

Sir / Madam,

As per your work order/request Geo-Hydrological / Geo-physical Survey carried out in your land / site belonging Bangalore city/village Kenchenahalli, Balaji Layout Dated on 24/09/17 in order to assess the ground water potential of the area for drinking / irrigation / industrial purposes.

The area inspected has a slope towards ..... marked by ..... Soil, uneven topography hydrogeological features are found to be favourable / not favourable for ground water extraction. Geology of the area is marked by ..... rock.

SOURCES EXTRACTED :

(I) Betwen 200.00 ft/mtrs. (II) 250.00 ft/mtrs.

(III) 270.00 ft/mtrs.

From the study of the above field observation, Investigation results, a borewell VES drilling .....to app depth of ..... ft/mtrs. Below the ground level, casing pipe required be to app depth of 130-180 ft/mtrs.

Approx, yield expected may be around 2 Inch GPH.

Suggested to drill 4 $\frac{1}{2}$" / 6 $\frac{1}{2}$" dia Borewell.

NOTE : Although the best site for drilling has been suggested, no guarantee of success can be given and we will not be liable in any way for any loss to the party in respect of the well drilled at the site recommended being a failure in any form.

Save Water

(NAGARAJ MOKASHI)

SAVE ENVIRONMENT **ADOPT RAINWATER HARVESTING**

Services : Ground Water location by geo-hydrological, geophysical and divining methods, Driling advisors and supervision. Rain Water harvesting, water shed management, Quarry operations, Planning, Water testing, Soil Testing & Surveying.

Am An GEO CONSULTANT

NAGARAJ MOKASHI, MSc.,
GEOLOGIST

Mobile : 94483 13401
e-mail : ngmokashi@rediffmail.com
am.an4geoconsultant@gmailcom
Ramjyothi Nagar, R.V.College Post, Bangalore - 560 059.

To,
AEE, BBMP
Yelahanka Sub Division.

AEE
Executive Engr
Yelahanka Sub Divis
(BBMP Y. K. Zn)
Yelahanka, Banga

Date : 01/10/17

GEO-TECHNICAL SURVEY REPORT
(Ground Water Exploration)

Sir / Madam,

As per your work order/request Geo-Hydrological / Geo-physical Survey carried out in your land / site belonging Bangalore city/village Edaga maidan (Bowrial Ground) W.No2 Dated on 1/10/17 in order to assess the ground water potential of the area for drinking / irrigation / industrial purposes.

The area inspected has a slope towards ..... marked by ..... Soil, uneven topography hydrogeological features are found to be favourable / not favourable for ground water extraction. Geology of the area is marked by ..... rock.

SOURCES EXTRACTED :

(I) Betwen 180.00 ft/mtrs. (II) 240.00 ft/mtrs.

(III) 280.00 ft/mtrs.

From the study of the above field observation, Investigation results, a borewell VES drilling .....to app depth of ..... ft/mtrs. Below the ground level, casing pipe required be to app depth of 150 To 180 ft/mtrs.

Approx, yield expected may be around 3 Inch GPH.

Suggested to drill 4 $\frac{1}{2}$" / 6 $\frac{1}{2}$" dia Borewell.

****

NOTE : Although the best site for drilling has been suggested, no guarantee of success can be given and we will not be liable in any way for any loss to the party in respect of the well drilled at the site recommended being a failure in any form.

Save Water

(NAGARAJ MOKASHI)

SAVE ENVIRONMENT **ADOPT RAINWATER HARVESTING**

Services : Ground Water location by geo-hydrological, geophysical and divining methods, Driling advisors and supervision. Rain Water harvesting, water shed management, Quarry operations, Planning, Water testing, Soil Testing & Surveying.

COMPLETION REPORT

VINAYAKA ENTERPRISES

Borewell Drilling Contractors

Mobile : +91 9342202932 / 9343202932

No. 9, Bhadrappa Layout, Bhadrappa Compound, Near Hebbal, Ring Road, Bangalore 560094

No. : 1178

Date : 28/2/14

1. Customer's Name and Address with Telephone No. : AEE, BBMP, Yelahanka Sub Division

Asst. Executive Engineer
Yelahanka Sub. Divison
(BBMP Tnk. Zn)
Yelahanka, Bangalore

2. Well Location : Avvalli Govt School Ward No.2

3. Total Well Depth / Drilled in Ft. : 285.00 Mtrs

4. Casing Erected in Ft. : 70.00 mtr

5. Water Struck at the Depth of : 800 To 900 ft

6. Total Yield (Measuring method "V" Norch : 2½ Inch / Inches on "V" Norch)

7. Formation of Soil/Well Water Condition : Boulders/Silt/Loose Soil/Clear clear

8. At the Depth of : 1100.00 feet

9. Recommended to use Jet Pump / Air Compressor / Submersible /Hand Pump

Submersible

The Borewell was drilled in accordance with the company terms and conditions and handed over to customer in good/ satisfied / Party agreed conditions.

Once the well handed over to party, company is no way responsible for further developments if anything in the well or what so ever.

Party's Signature

I, owner of the Well / (Authorised signatory) fully understood the terms and conditions and the well completion report, I also fully understood the quality and quantity of water from the well duly depend upon the nature / formation of ground water and the drilling agency no way responsible for further occurrence / Changes in the bore with full satisfaction. I hereby endorse my signature.

For VINAYAKA ENTERPRISES

Manager / Proprietor

Party's Signature

COMPLETION REPORT

VINAYAKA ENTERPRISES

Borewell Drilling Contractors

Mobile : +91 9342202932 / 9343202932

No. 9, Bhadrappa Layout, Bhadrappa Compound, Near Hebbal, Ring Road, Bangalore 560094

No. : 1177

Date : _____

1. Customer's Name and Address with Telephone No. : K.E.C BBMP. Yelahanka Sub Division

2. Well Location : K.E.B. Layout harohalli Ward No. 2

3. Total Well Depth / Drilled in Ft. : 290 To 310 mtrs

4. Casing Erected in Ft. : 75.0mtrs

5. Water Struck at the Depth of : 900 To 950 feet

6. Total Yield (Measuring method "V" Norch : 2 Inches / Inches on "V" Norch)

7. Formation of Soil/Well Water Condition : Boulders/Silt/Loose Soil/Clear Clear

8. At the Depth of : 1100.00 feet

9. Recommended to use Jet Pump / Air Compressor / Submersible /Hand Pump

The Borewell was drilled in accordance with the company terms and conditions and handed over to customer in good/ satisfied / Party agreed conditions.

Once the well handed over to party, company is no way responsible for further developments if anything in the well or what so ever.

Party's Signature

I, owner of the Well / (Authorised signatory) fully understood the terms and conditions and the well completion report, I also fully understood the quality and quantity of water from the well duly depend upon the nature / formation of ground water and the drilling agency no way responsible for further occurrence / Changes in the bore with full satisfaction. I hereby endorse my signature.

For VINAYAKA ENTERPRISES

~~Manager~~ / Proprietor

Party's Signature

BOREWELL
COMPLETION REPORT

VINAYAKA ENTERPRISES

Borewell Drilling Contractors

Mobile : +91 9342202932 / 9343202932

No. 9, Bhadrappa Layout, Bhadrappa Compound, Near Hebbal, Ring Road, Bangalore 560094

No. : **1176**

Date : 10/2/16

1. Customer's Name and Address with Telephone No. : AEE, BBMP, Yelahanka Sub Division

Executive Engineer
ASST. Executive Engineer
Yelahanka Sub. Division
BBMP Ynk. Zn Bgon
Yelahanka, Bangalore

2. Well Location : Kempechenahalli, Balaji Layout Ward No. 2

3. Total Well Depth / Drilled in Ft. : 310.00 mtr

4. Casing Erected in Ft. : 65.0 mtr

5. Water Struck at the Depth of : 750 To 800 (or) 900 feet

6. Total Yield (Measuring method "V" Norch : 3 Inches / Inches on "V" Norch)

7. Formation of Soil/Well Water Condition : Boulders/Silt/Loose Soil/Clear ✓ clear

8. At the Depth of :

9. Recommended to use Jet Pump / Air Compressor / Submersible ✓ /Hand Pump

The Borewell was drilled in accordance with the company terms and conditions and handed over to customer in good/ satisfied / Party agreed conditions.

Once the well handed over to party, company is no way responsible for further developments if anything in the well or what so ever.

Party's Signature

I, owner of the Well / (Authorised signatory) fully understood the terms and conditions and the well completion report, I also fully understood the quality and quantity of water from the well duly depend upon the nature / formation of ground water and the drilling agency no way responsible for further occurrence / Changes in the bore with full satisfaction. I hereby endorse my signature.

For VINAYAKA ENTERPRISES

Party's Signature

~~Manager~~ / Proprietor

BOREWELL COMPLETION REPORT

VINAYAKA ENTERPRISES

Borewell Drilling Contractors

Mobile : +91 9342202932 / 9343202932

No. 9, Bhadrappa Layout, Bhadrappa Compound, Near Hebbal, Ring Road, Bangalore 560094

No. : 1175

Date : _____

1. Customer's Name and Address with Telephone No. : AEE. BBMP Yelahanka Sub Division

2. Well Location : Eduga Maidan (Bourial Ground) WI No. 2

3. Total Well Depth / Drilled in Ft. : 320.00mtr

4. Casing Erected in Ft. : 70.00mtr

5. Water Struck at the Depth of : 280.00mtr

6. Total Yield (Measuring method "V" Norch : 3 Inches / Inches on "V" Norch)

7. Formation of Soil/Well Water Condition : Boulders/Silt/Loose Soil/Clear ✓ clear

8. At the Depth of :

9. Recommended to use Jet Pump / Air Compressor / Submersible ✓ /Hand Pump

The Borewell was drilled in accordance with the company terms and conditions and handed over to customer in good/ satisfied / Party agreed conditions

Once the well handed over to party, company is no way responsible for further developments if anything in the well or what so ever.

Party's Signature

I, owner of the Well / (Authorised signatory) fully understood the terms and conditions and the well completion report, I also fully understood the quality and quantity of water from the well duly depend upon the nature / formation of ground water and the drilling agency no way responsible for further occurrence / Changes in the bore with full satisfaction. I hereby endorse my signature.

For VINAYAKA ENTERPRISES

Party's Signature

~~Manager~~ / Proprietor

Executive En
Yelahanka Sub. Di
(BBMP Ynk. Z
Yelahanka, Ban